BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Maintenance of Electrical cremetorium building in hebbal in ward no. 7 Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	120.00	KSRRB 300-1. Earthwork excavation and forming in embankment by manual means in rodinary soil(when earth is taken from bank cutting or from borrow pits) including breaking of clods, spreading to required line and level, forming and cost of all labour complete as per specifications.. Pg No.142.Item No.19.3)	cum	112.32	Rupees One Hundred Twelve and Thirty Two Paise Only
2	37.50	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)	cum	5256.36	Rupees Five Thousand Two Hundred Fifty Six and Thirty Six Paise Only
3	25.00	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.69 cum and fine aggragtes @ 0.459cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications. (Page No. 12. Item No. 4.6)	cum	5876.28	Rupees Five Thousand Eight Hundred Seventy Six and Twenty Eight Paise Only
4	60.00	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. Specification No. KBS. (P.No. 101, I.No. 14.6 of CSR 2016-17)	Sqm	984.96	Rupees Nine Hundred Eighty Four and Ninety Six Paise Only

Sl. No	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	100.00	Providing flooring with cement design concrete design concrete tiles of aproved colour designfor external flooring to the floor . The thickness of the tiles should be minimum of 10mmand should have compressive strength of M-52 confirming to IS 1237-1980 Specifications fixing in cement mortar 1:3and using reodixed colour to fill the joints btween the tiles etc., complete including the cost of material, labour, transporatation, all taxes charges etc., as per instruction of Engineer in charges, ultra tiles pebble beach grey colour (Data Rate) as approved by EIC VIDE LETTER nO.1736/09-10 DT. 20/1/09	Sqm	1375.00	Rupees One Thousand Three Hundred Seventy Five Only
6	90.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete. Page No. 25 / Item No. 5.29.1	Nos	393.12	Rupees Three Hundred Ninety Three and Twelve Paise Only
7	40.50	Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. Page No. 122 / Item No. 15.80	Sqm	28.08	Rupees Twenty Eight and Eight Paise Only
8	34.00	Providing and fixing Ornamental benches (Delhi benches) as per design, drawing specification and directions of Engineer in charge.	Sqm	8500.00	Rupees Eight Thousand Five Hundred Only
9	120.00	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	cum	106.00	Rupees One Hundred Six Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be
2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

Chief Engineer
Yelahanka Zone
Bath Bangalore Mahanagara
Bangalore 92